BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI

Office of the Executive Engineer Dasarahalli Division,

Tender No: BBMP/EE/DD/TEN/ 02 /12-13 Date:19.05.2012 Item No: 25

SCHDULE-B

Name of Work:Construction of RCC Drain at Manjunathanagara 6th Cross in ward no.14 T.Dasarahalli Sub Division.Dasarahalli Zone.

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed the disposed earth to be leveled neatly after breaking of clods complete as per specifications.	Cum	279.30	91.00	Rupees Ninety One Only
2	Plain cement concrete 1:3:6 mix with crushed stone aggregates 40m nominal size mechanically mixed, placed in foundation and compacted by vibration including curing for 14days complete as per specifications.	Cum	47.88	3677.00	Rupees Three Thousand Six Hundred Seventy Seven Only
3	Providing and laying in position reinforced cement concrete of mix M15 with OPC cement @ 240kgs,with 20mm and down size graded granite metal Coarse aggregates @ 0.878cum and fine aggregates @0.459cum machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for R.C.C beams, columns of all sizes in foundation plinth and Superstructure ground floor level for roof slabs, staircase, lintels columns, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	105.74	4494.00	Rupees Four Thousand Four Hundred Ninety Four Only
4	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post and struts, square / rectangular / polygon in plan including cost of all materials, labour complete as per specifications.	Sqm	957.60	284.00	Rupees Two Hundred Eighty Four Only
5	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Qtls	42.29	6577.00	Rupees Six Thousand Five Hundred Seventy Seven Only

C Puneeth

Signature Of The Contractor

Executive Engineer

6	Providing & Laying Reinforced cement precast slabs of mix M20 Using 20mm & down size graded granite metal using HYSD 10mm dia steel @100mm c/c both ways & complete as per specfications.	Sqm	239.40	2062.00	Rupees Two Thousand Sixty Two Only
7	Providing & fixing pre cast solid concrete Kerb stones made out of CC 1:2:4 of size 450x200x400 mm and finished with CM 1:3 plastering and finishing cutting etc.,	No	1190.00	299.00	Rupees Two Hundred Ninety Nine Only
8	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 15 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	270.00	82.00	Rupees Eighty Two Only

C Puneeth

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,
B.B.M.P. Bangalore